

Got a big site and need a big solution? Choose a 40ft container room instead of two 20ft units. Safe and quick to deploy onsite.

Details

Built with the same high-quality materials as our standard containers and portable buildings, the SCF 40ft Container Office/ Lunch Room is a dedicated space for your team and contractors to safely manage projects, eat lunch, enjoy hot or cold drinks, and light refreshments throughout the day. The 40ft unit is particularly popular for sites that require multiple rooms and levels for the workforce. Halve the lifting requirements by using 1 x 40ft container instead of 2 x 20ft containers.

SCF 40ft Site Sheds are installed with Rockwool insulation, split system reverse cycle air conditioning, hot and cold water, sink, stainless steel kitchenette bench and energy efficient internal lighting. There are also provisions for an optional microwave and refrigerator, which can be installed in depot prior to delivery. A team who can eat in comfort and refuel will get more work done with less mistakes.

Key Features

- Double stackable 1x 40ft or 2 x 20ft containers
- Rockwool insulation
- Split system reverse cycle air conditioning externally recessed (within each 20ft footprint)
- Hard wired smoke detector with battery backup
- Steel PA doors with lockbox
- Windows with flyscreen and security mesh
- Approx 12.2m L x 2.5m W x 2.9m

Options

- Multiple fitout options 2 x Container Offices, 2 x Lunch Rooms, 1 of each, or open plan Lunch Room
- Adequate table and seating for your team depending on your configuration

Specifications40ft Office And Lunch Room

0	:6:+			
Spec	aricari	ons	mav	varv

External			
Length (mm)	12,192		
Width (mm)	2,438		
Height (mm)	2,896		

Internal				
Length (mm)	11,904			
Width (mm)	2,150			
Height (mm)	2,402			

Weight			
Tare (kg)	5,000		
Payload (kg)	10,000		
MGW (kg)	15,000		



